Issue	Date	Amendment
A	25.11.02	EXISTING CHIMNEY REMOVED
B	08.08.03	EXTENSION REDUCED IN WIDTH TO 2.4m - DR.

Job: EXTENSION
34 WILLOUGHBY DRIVE
EMPINGHAM

James Richardson
Design Consultant
14 King Edwards Way, Edith Weston, Rutland LE15 8EZ

Drawing: FRONT (NORTH) ELEVATION AS PROPOSED

Scale: 1:50 | Date: 01.11.02 | Drawn | Approved

Status: PLANNING

Drawing No. 02/1911/113 B

FUL/2002/1029

MINOR AMENDMENT
approved by letter
dated 27.08.03
showing Reduction in width of extension



CONCRETE INTERLOCKING TILES TO MATCH EXISTING ROOF.

RAINWATER GOODS AND FASCIA CLADDING IN WHITE PVC-U TO MATCH EXISTING.

NEW WHITE PVC-U WINDOW TYPE TO MATCH EXISTING.

BRICKWORK FACINGS TO MATCH EXISTING.

CONC. INT. ROOF TILES TO MATCH EXISTING.

PVC-U R/W GOODS IN WHITE.

EXISTING GARDEN WALL CUT BACK FOR NEW GATE POSITION.

EXISTING METAL GATE TO BE RE-USED

NEW BRICK PIER

NEW CASEMENT WINDOW IN WHITE PVC-U.

NEW DOOR AND SIDE LIGHTS IN EXISTING OPENING.

NEW WHITE UP & OVER GARAGE DOOR.

LINE OF BOUNDARY

NEIGHBOURING PROPERTY

FRONT NORTH ELEVATION — AS PROPOSED

1:50

RUTLAND COUNTY
12 AUG 2003
COUNCIL DC